



## भारतीय प्रौद्योगिकी संस्थान हैदराबाद

कंडी - ५०२ २८५, सांगारेड्डी, तेलंगाना, भारत

फोन : ०४० २३०१ ६००१; फैक्स : (०४०) ६००३ / ३२

Indian Institute of Technology Hyderabad

Kandi - 502 285, Sangareddy, Telangana, INDIA

Phone: (040) 2301 6091; Fax: (040) 2301 6003 /32

Construction and Maintenance Division

### NOTICE INVITING QUOTATION

NIQ No: 04/NIQ/IITH/CMD/2020-21

Date: 24<sup>th</sup> July 2020

The Executive Engineer (Civil), Indian Institute of Technology Hyderabad, Kandi, Sangareddy - 502 285 invites on behalf of the IITH sealed item rate quotations for following work from the approved and eligible contractors of CPWD and those of appropriate list of MES, BSNL, Railway, PWD (B&R), working contractors of IIT Hyderabad or Specialized agencies in making SS Signage Name Boards.

The quotations should be sent in a sealed cover addressed to **"The Executive Engineer (Civil), Construction and Maintenance Division, Indian Institute of Technology Hyderabad, Kandi, Sangareddy (Dist) Telangana State- 502 285"** super scribing the name of work.

**NAME OF WORK:** Providing and fixing of SS Name boards (Building Signage) in English for Main Hostel blocks(10Nos) and PSH (01 Nos) at IIT Hyderabad, Kandi Campus(2<sup>nd</sup> Call).

Estimated Cost : Rs.6,65,738/-

EMD : Rs.13,400/-

*(The EMD shall be form of Demand Draft Drawn in any Scheduled bank in favour of Indian Institute of Technology Hyderabad, payable at SBI, IIT Hyderabad Branch).*

Time for Completion of Work : 30 Days


Last Date of Receipt of Quotations : 04-08-2020@3PM

Date of Opening of Quotations : 04-08-2020@4PM

Validity of Quotations : 30 Days

Conditional Quotations or Quotations with conditional rebate shall be summarily rejected.

Yours faithfully,

  
Executive Engineer (C)  
IIT Hyderabad

#### NOTE:

- 1). Downloaded quotations are accepted.
- 2). Quotations received through Speed post or Courier within the time limit shall be accepted.

## SCHEDULE OF QUANTITIES

Name of the work: Providing and fixing of SS Name boards( Building Signage)in English for Main Hostel blocks(10Nos)and PSH(01 Nos) at IIT Hyderabad, Kandi Campus(2nd Call).

S.No	Description of Item	Unit	Qty	Rate(Rs.)		Amount(Rs.)
				In Figures	In Words	
1	Supply of SS 304 Grade Letters, design names having front face thickness of 1.00mm and side face of all-round 0.8mm thick and thickness (Width) of the Each Letter is 38.10mm. The Dimension width of Each Letter is 0.45M and Height of Each Letter is 0.60 M including making ,cutting ,transportation charges of all materials to site etc, complete and as per direction of Engineer in Charge.	Each	174.00			
2	Fixing of SS 304 Grade Letters, design names having front face thickness of 1.00mm and side face of all-round 0.8mm thick and thickness (Width) of the Each Letter is 38.10mm. The Dimension width of Each Letter is 0.45M and Height of Each Letter is 0.60 M including necessary arrangements of drilling holes,fixing fastners of all materials to site etc, complete and as per direction of Engineer in Charge.	Each	174.00			
3	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners,connection with the building etc wherever required for inspection of work at required locations with essential safety features for theworkmen etc. complete as per directions and approval of Engineerin-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.	Sqm	342.00			

*Signature*



S.No	Description of Item	Unit	Qty	Rate(Rs.)		Amount(Rs.)
				In Figures	In Words	
4	Supply and fixing of HILTI STD stud Anchor fastner HAS-R M8X70 of standard expansion anchor for uncracked concrete (Grade SS 316) including transportation charges of all materials to site etc, complete and as per direction of Engineer in Charge.	Each	522.00			
<b>TOTAL AMOUNT IN RUPEES</b>						


  
 24/12/2020  
 ASSISTANT EXECUTIVE ENGINEER(CIVIL)


  
 EXECUTIVE ENGINEER(CIVIL)

CONTRACTORS' SIGN AND SEAL